

1 050459

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 093-20,037-0001

C NE SE       , SEC. 32, T 21 S, R 35 (W) X

1980 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6234

Lease Name Miller "A" Well # 1

Operator: The Maurice L. Brown Company

County Kearny 164.62

Name & Address 200 Sutton Place Building

Well Total Depth 5065 feet

Wichita, KS 67202

Conductor Pipe: Size        feet

Surface Casing: Size 8 5/8 feet 366

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated       

Plugging Contractor Midwest Casing Pulling License Number 6497

Address P. O. Box F, Sublette, KS 67879

Company to plug at: Hour: 1:00 pm Day: 19 Month: February Year: 19 85

Plugging proposal received from Ed Eves

(company name) Midwest (phone) 316-675-8349

were: 5 1/2" set at 4602' Perfs at 4545-49'

1st plug pump 2 sx hulls and 20 sx cement to bottom

Spot plugs through 4 1/2" with mud between plugs

2nd plug at 900' with 50 sx cement

3rd plug at 400' with 40 sx cement  
solid bridge

4th plug hulls - plug at 40' Plugging Proposal Received by Richard W. Lacey  
cement to surface with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3:00 pm Day: 19 Month: February Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement to bottom, spotted

plugs through 4 1/2" with mud between plugs, 2nd plug at 900' with 50 sx cement, 3rd plug

at 400' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement

to surface with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 25 1985  
2-25-85

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Recovered 955' 5 1/2" casing. Used Common cement by Midwest

(If additional description is necessary, use BACK of this form.)

INVALED (and not) observe this plugging.

DATE 2-27-85

Signed Richard W. Lacey  
(TECHNICIAN)

INV. NO. 1163

2-19