

1 030430

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,188-0000
SW SE SE, SEC. 3, T 21 S, R 25 W/E

330 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6462

Lease Name Gross Well # 1-979

Operator: Kennedy & Mitchell, Inc.

County Hodgeman 144.66

Name & Address Box 1788

Well Total Depth 4451 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 513

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 8:00 am Day: 15 Month: May Year: 19 85

Plugging proposal received from Doug Blair

(company name) Sargent's (phone) 316-624-7455

were: 5 1/2" at 4448' Perfs at 4436-42' PBTD 4448'

1st plug pump 1 sack hulls and 25 sx cement to bottom. Shoot off pipe. Load hole with mud and spot through tubing.

2nd plug at 1600' with 50 sx cement 3rd plug at 850' with 50 sx cement
solid bridge

4th plug at 560' with 40 sx cement 5th plug hulls - plug at 40' --- cement to
surface with 10 sx cement

Plugging Proposal Received by Robert B. Tarbutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5:00 pm Day: 17 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 1 sack hulls and 25 sx cement to bottom, 2nd plug at 1600' with 50 sx cement, 3rd plug at 850' with 50 sx cement, 4th plug at 560' with 40 sx cement, 5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

6-17-85 JUN 17 1985

Remarks: Recovered 2438' 5 1/2" casing. Used common cement by Sargent's
(If additional description is necessary, use BACK of this form.)

INVOICED

(xxx did not) observe this plugging.

DATE 6-20-85

Signed Steve Stewart
(TECHNICIAN)

INV. NO. 8639

JUN 25 1985