

DEC 7 1988

API NUMBER 15- NA

1 120175

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW, SEC. 19, T 21 S, R 25 W 7E

3300 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4704

Lease Name Jackson Ranch Well # 1

Operator: True Oil

County Hodgeman 145.54

Name & Address P.O. Box 2360

Well Total Depth 4478 feet

Casper, Wyoming 82602

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 709

Abandoned Oil Well Gas Well Input Well SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor Cheyenne Oil Service License Number 7146

Address 118 North Penn, Ness City, KS 67560

Company to plug at: Hour: 10 a.m. Day: 7 Month: 12 Year: 19 88

Plugging proposal received from John Carley

(company name) Cheyenne Oil Service (phone) 913-798-2282

were: 4 1/2" at 4478' cemented w/125 sx cement Perfs at 4362-67'

1st plug sand back to 4310' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release plug and pump 110 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12 p.m. Day: 7 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped into 4 1/2" casing with 250 lbs. hulls, and 130 sx cement. Pumping pressure 0-450 psi and shut in 300 psi.

2nd plug pumped into 4 1/2" X 8 5/8" annulus with 50 lbs. hulls and 100 sx cement.

Pumping pressure 0-800 psi and shut in 550 psi.

12-13-88
RECEIVED
STATE CORPORATION COMMISSION

DEC 13 1988

Remarks: Used Econolite by HOWCO. No casing recovery.
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED (did not observe this plugging.)

Signed *Deanna Rankin* (TECHNICIAN)

DATE 12-13-88

INV. NO. 23347 12-7