

1 070227

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-083,21,262-0000
NW SE NE SEC. 19, T 21 S, R 25 W/R
3550 feet from S section line
810 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4704

Lease Name Stueckemann Well # 42-19

Operator: True Oil Company
Name & Address P.O. Box 2360
Casper, Wyoming

County Hodgeman 146.25

Well Total Depth 4500 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 724

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor True Drilling Company License Number 4708

Address Casper, Wyoming

Company to plug at: Hour: 5:30 p.m. Day: 1 Month: 10 Year: 19 86

Plugging proposal received from Buzz Montgomery

(company name) True Oil Company (phone) 307-746-9767

Remarks: To fill hole with heavy mud and spot cement through drill pipe Elevation 2345' GL
Anhydrite 1537-46'

1st plug at base of Anhydrite with 15 sx cement

2nd plug at 30' below surface casing with 50 sx cement

3rd plug at 40' below surface with 10 sx cement

4th plug to circulate rathole with 15 sx cement

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 8:30 p.m. Day: 1 Month: 10 Year: 1986

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement

2nd plug at 750' with 50 sx cement

3rd plug at 40' with 10 sx cement

4th plug to circulate rathole with 10 sx cement

5th plug to circulate mousehole with 10 sx cement

RECEIVED
STATE CORPORATION COMMISSION
CONS. DIV. WICHITA, KS

10-3-86
OCT 3 1986

Remarks: Used 60/40 Pozmix 6% gel by Halliburton
(if additional description is necessary, use BACK of this form.)

INVOLCED

It is recommended that you observe this plugging.

DATE 10-3-86

Signed Dan Anderson
(TECHNICIAN)

INV. NO. 15108

10-1

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 9/22/86 month day year 3:25

API Number 15-083-21,262-0000

OPERATOR: License # 4704 Name True Oil Company Address P.O. Box 2360 City/State/Zip Casper, Wyoming Contact Person C.F. Pickard Phone 307-266-0230

App. NW SE NE Sec. 19 Twp. 21 S, Rg. 25. 3550 Ft. from South Line of Section 810 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line .810 feet County Hodgeman Lease Name Stueckemann Well # 42-19 Ground surface elevation 2345 feet MSL Domestic well within 330 feet: Est yes X no Municipal well within one mile: yes X no

CONTRACTOR: License # 4708 Name True Drilling Company City/State Casper, Wyoming 82602 Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield Mud Rotary Gas Inj X Pool Ext Air Rotary OWWO Expl Wildcat Cable

Depth to bottom of fresh water 200 Depth to bottom of usable water 700 Surface pipe by Alternate 1 X 2 Surface pipe planned to be set 700 Conductor pipe required n/a Projected Total Depth 4500 Formation Mississippian

if OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 9/19/86 Signature of Operator or Agent Vera Elmore Title as agent

for KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 70.0 feet per Alt. This Authorization Expires 3-19-87 Approved By 9-19-86

SPUD - 9-23-86 - 10:00A

SP = 700' will call for plugging just if needed

app. NW SE NE Sec. 19 Twp. 21 S, Rg. 25. East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ Base of Anhydrite feet depth with 15 sxs of cement 2nd plug @ 30' below surface feet depth with 50 sxs of cement 3rd plug @ 40' below surface feet depth with 40 sxs of cement 4th plug @ feet depth with sxs of 5th plug @ feet depth with sxs of 2) Rathole with 15 sxs (b) Mousehole with sxs

307-746-4161 PUSHER Buzz Montgomery TD 4500 FORMATION SURFACE PIPE 8 3/8 @ 224 ANHYDRITE 15' ELEVATION 37-46 STARTING TIME & DATE 5:30 pm - 10-1 COMPLETION TIME & DATE 8:30 pm - 10-1 1st PLUG @ 1530 FT. W/ 50 SX 2nd PLUG @ 750 FT. W/ 50 SX 3rd PLUG @ 40 FT. W/ 10 SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ 10 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ SX CEMENT COMPANY Halliburton TECHNICIAN Mrs. Goodwin 60/40 6/9/86