

12-30

1 040210

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 083-21,316-0000

TECHNICIAN'S PLUGGING REPORT

Operator License # 5195

Operator: Resource Ventures Corporation
Name & Address: 1501 Superior Street
Lincoln, NE 68521

SE NE SW, SEC. 19, T 21 S, R 25 W/8

1650 feet from S section line

3050 feet from E section line

Well # 1

County Hodgeman

Well Total Depth 4500 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 207

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor: Blue Goose Drilling Company, Inc. License Number 5104

Address: Box 1413, Great Bend, KS 67530

Company to plug at: Hour: 6 a.m. Day: 30 Month: 12 Year: 19 88

Plugging proposal received from Martin Miller

(company name) Blue Goose Drilling Company, Inc. (phone) 316-792-5633

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1533-46'

1st plug at 1546' with 50 sx cement, 2nd plug at 770' with 80 sx cement,

3rd plug at 240' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Stephen J. Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 8 a.m. Day: 30 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 1546' with 50 sx cement,

2nd plug at 770' with 80 sx cement,

3rd plug at 240' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
did not observe this plugging.

DATE 1-9-89

INV. NO. 23564

Signed Stephen J. Pfeifer (TECHNICIAN)

12-30

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... December 19, 1988

API Number 15-083-21,316-0000

OPERATOR: License # 5195
Name Resource Ventures Corporation
Address 1501 Superior Street
City/State/Zip Lincoln, NE 68521
Contact Person Roger Rhodes
Phone 402.435-3535

Appx SE NE SW Sec. 19 Twp. 21 S. Rg. 25
1650 Ft. from South Line of Section
3050 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 1600 feet
County Hodgeman

CONTRACTOR: License # 5104
Name Blue Goose Drilling Co., Inc.
City/State Great Bend, KS 67530

Lease Name Stueckemann Well # 1

Well Drilled For: Well Class: Type Equipment:
X Oil Storage Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl X Wildcat Cable

Ground surface elevation 2329 feet MSL

Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no

Depth to bottom of fresh water 350'
Depth to bottom of usable water 500' 550'

Surface pipe by Alternates 1 2X

If OWWO: old well info as follows:

Surface pipe planned to be set 200'
Conductor pipe required N/A

Operator
Well Name
Comp Date Old Total Depth

Projected Total Depth 4550' feet
Formation Mississippi

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 14 Dec 88 Signature of Operator or Agent Title Geologist

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt. X 2

This Authorization Expires Approved By LKM 12-14-88

EFFECTIVE DATE: RECEIVED STATE CORPORATION COMMISSION 5-88 Spud 12-18-88, 8 5/8" - 200' +

RECEIVED STATE CORPORATION COMMISSION 5-88
JAN - 4 1989
CONSERVATION DIVISION
Wichita, Kansas

YES
W/W

Sec. 19 Twp. 21 S. Rg. 25 East XX West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays). Operator/Contractor will contact District Office for plugging orders after determining depth of anhydrite.

- 1st plug @ ft. deep... or formation with... feet of...
2nd plug @ ft. deep... or formation with... feet of...
3rd plug @ ft. deep... or formation with... feet of...
4th plug @ ft. deep... or formation with... feet of...
5th plug @ ft. deep... or formation with... feet of...
(2) Rathole to surface minus 5 feet (b) Mousehole to surface minus 5 feet

Drig. @ 4375'
PUSHER Martin Miller
TD 4500 FORMATION
SURFACE PIPE 8 5/8" @ 207'
ANHYDRITE 1533 ELEVATION 2329.64
STARTING TIME & DATE 6:00 am 12-30-88
COMPLETION TIME & DATE 8:00 am 12-30-88
1st PLUG @ 1546 FT. WI 50 SX
2nd PLUG @ 770 FT. WI 80 SX
3rd PLUG @ 240 FT. WI 40 SX
4th PLUG @ 40 FT. WI 10 SX
RAT HOLE CIRCULATED WI 15 SX
MOUSE HOLE CIRCULATED WI none. SX
WATER WELL PLUGGED WI NO wt. well SX
CEMENT COMPANY Allied
TECHNICIAN S.P.
60/40 poz. w/ 6" gel