

To: 1 040794 10-17  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-083-21,402-0000  
NW NW SE, SEC. 19, T 21 S, R 25 W/X  
2310 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3447  
Operator: Ranken Energy Corporation  
Name & Address: 601 N. Kelly, Ste. 103  
Edmond, OK 73003-4855

Lease Name Sinclair Well # 1-19  
County Hodgeman 143.81  
Well Total Depth 4425 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 206

Abandoned Oil Well Gas Well Input Well SHD Well D&A X

Other well as hereinafter indicated

Plugging Contractor L.D. Drilling, Inc. License Number 6039

Address RR 1, Box 183 B, Great Bend, KS 67530

Company to plug at: Hour: 2 a.m. Day: 17 Month: 10 Year: 19 93

Plugging proposal received from Greg Davidson

(company name) L.D. Drilling, Inc. (phone) 316-793-3051

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1530-60'

1st plug at 1560' with 50 sx cement, 2nd plug at 800' with 80 sx cement,

3rd plug at 230' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:30 a.m. Day: 17 Month: 10 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 1560' with 50 sx cement,

2nd plug at 800' with 80 sx cement,

3rd plug at 230' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Halliburton.

INVOICED

(If additional description is necessary, use BACK of this form)

DATE NOV 02 1993 observe this plugging.

INV. NO. 39084

Signed Stephen J. Pfeifer (TECHNICIAN)  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

10-20-93

NOV 20 1993

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date: 10 04 93 month day year

Spot VNW NW SE Sec 19 Twp 21 S. Rg 25 East West

OPERATOR: License # 3447 Name: Ranken Energy Corporation Address: 601 N. Kelly, Ste 103 City/State/Zip: Edmond, OK 73003-4855 Contact Person: Tom Larson Phone: 316/653-7368

2310 feet from South North line of Section 2310 feet from East West line of Section IS SECTION REGULAR X IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side) County: Hodgeman Lease Name: Sinclair Well #: 1-19 Field Name: Wildcat Is this a Prorated/Spaced Field? yes X no Target Formation(s): Mississippian Nearest lease or unit boundary: 330' Ground Surface Elevation: 2329 feet MSL Water well within one-quarter mile: yes X no Public water supply well within one mile: yes X no Depth to bottom of fresh water: 70' Depth to bottom of usable water: 750' Surface Pipe by Alternate: 1 X 2 Length of Surface Pipe Planned to be set: 200' Length of Conductor pipe required: N/A Projected Total Depth: 4450' Formation at Total Depth: Mississippian Water Source for Drilling Operations: well farm pond X other DWR Permit #: Will Cores Be Taken?: yes X no If yes, proposed zone:

CONTRACTOR: License #: 6039 Name: L. D. Drilling, Inc.

Well Drilled For: Well Class: Type Equipment: X Oil ... Enh Rec ... Infield X Mud Rotary ... Gas ... Storage ... Pool Ext. ... Air Rotary ... OWD ... Disposal X Wildcat ... Cable ... Seismic: ... # of Holes ... Other If OWD: old well information as follows: Operator: Well Name: Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: Bottom Hole Location: Exp. 3/27/94

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq. It is agreed that the following minimum requirements will be met:

Pusher Greg Davidson SPUD DATE 10-08-93 INIT. GB LENGTH SURFACE PLANNED 200' RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 3/8 @ 206 CONDUCTOR ANHYDRITE T-1530 B-1560 ELEVATION (4260) TD 4425 FORMATION 1CB 232L AN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 1560 Ft. W/ 50 SX 1/2 Base Anyh. @ 800 Ft. W/ 80 SX 1/2, 1/2 Plug @ Ft. W/ SX Bottom Surface @ 230 Ft. W/ 40 SX 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN SP DATE 10-15-93 Hauling RECEIVED STATE OIL AND NATURAL GAS COMMISSION WICHITA, KANSAS STARTING TIME 2:00 (AM/PM) DATE 10-17-93 COMPLETION TIME 4:30 (AM/PM) DATE 10-17-93 TYPE OF CEMENT 60/40 grs 6 gal 1/4 flow-head CEMENT COMPANY Halliburton