

R

1 050659

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-083-20,055

SE, SEC. 2, T 21 S, R 26 W/8

660 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5692

Lease Name Cheney Well # 2 SWD

Operator: American Petrofina

County Hodgeman 142.87

Name & Address P.O. Box 209

Well Total Depth 4396 feet

Russel, KS

Conductor Pipe: Size _____ feet

67665

Surface Casing: Size 8 5/8 feet 276

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing Co Inc License Number _____

Address _____

Company to plug at: Hour: 11:00 am Day: 6 Month: November Year: 1985

Plugging proposal received from Ron Tiffen

(company name) American Petrofina (phone) _____

were: To pump down 4 1/2" casing with 25x hulls -

100sx of cement - 15sx gel - 4 1/2" wiper plug - 160sx cement.

4 1/2" set @ 4390 4 1/2" second staged @ ~~1609~~ 1609'

Cement circulated from 1609' to 0'

Open hole from 4390' to 4396

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:00 pm Day: 6 Month: November Year: 1985

ACTUAL PLUGGING REPORT Pumped down 4 1/2" casing with 25x hulls

100sx of cement - 15sx gel - 4 1/2" wiper plug - 160sx cement

Max Pump pressure 500 psi

Shot in pressure 100 psi

Was a Salt Water Disposal Docket # E-14,869

4 1/2" casing had holes from 3600' to 4390'

Remarks: Allied Cementing pumped 60/40 pozmix 6% gel for cement

(if additional description is necessary, use BACK of this form.)

RECEIVED

INVOICED

DATE 11-21-85

NOV 14 1985

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 11086

JAN 15 1986 CONSERVATION DIVISION
Wichita, Kansas MAR 27 1986

OCT 15 1986