

To: 1080037
STATE CORPORATION COMMISSION
Wichita, State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 093-20,661-0000

SW SW NE SW, SEC. 9, T 21 S, R 38 W/X

4-25
TECHNICIAN'S PLUGGING REPORT

Operator License / 5249

Lease Name John Well / 1A

Operator: Osborn Heirs Company

County Kearny 99.12

Name & Address P.O. Box 17968

Well Total Depth 3050 feet

San Antonio, TX 78286

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 335

Abandoned Oil Well Gas Well X Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address

Company to plug at: Hour: 10:15 a.m. Day: 25 Month: 4 Year: 19 96

Plugging proposal received from Dale Taylor

(company name) Osborn Heirs Company (phone) 316-373-2701

logs: 5 1/2" at 3048' w/700 sx cement, PBSD 3047', Perfs at 2894-2914, 2946-2970

1st plug pump down 5 1/2" with 500 lbs. hulls and 225 sx cement.

Check annulus.

4-31-96

RECEIVED
AMSBAS
CORP
APR 31 P 12:02

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11 a.m. Day: 25 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 500 lbs. hulls and 225 sx cement. Maximum pressure 150 psi and shut in 100 psi.

2nd plug pumped down 8 5/8" X 5 1/2" with 35 sx cement. Shut in pressure 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby authorize to conserve this plugging.

MAY 06 1996

Signed Kevin D Strube
(TECHNICIAN)

DATE

INV. NO. 45524