

1 020055

FEB 6 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-055-20,698-0000
37' WNW
C SW SW, SEC. 20, T 21 S, R 33 (W/R)
660 feet from S section line
4657 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5476

Lease Name Savolt Well # 1-A
County Finney 155.68

Operator: DNB Drilling, Inc.
Name & Address 535 North Oliver
Wichita, KS 67208

Well Total Depth 4790 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 433

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382

Address W. Hwy 50, Box 916, Garden City, KS 67846

Company to plug at: Hour: 1 a.m. Day: 6 Month: 2 Year: 19 87

Plugging proposal received from Jack Pepper

(company name) Cheyenne Drilling, Inc. (phone) 316-277-2062

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2040'
Elevation 2925'

1st plug at 2100' with 50 sx cement, 2nd plug at 1250' with 60 sx cement,

3rd plug at 900' with 50 sx cement, 4th plug at 450' with 25 sx cement,

5th plug to circulate rathole with 15 sx cement, 6th plug to circulate mousehole with

10 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4:20a.m. Day: 6 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2040' with 50 sx cement,

2nd plug at 1120' with 80 sx cement,

3rd plug at 460' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. 2-9-87
(If additional description is necessary, use BACK of this form.)

INVOICED (If applicable) observe this plugging.

DATE 2-9-87

Signed Glenn L. Barkley (TECHNICIAN) FEB 9 1987
CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 16103 MAR 27 1987
2-6

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date 1 28 87 month day year

API Number 15-055-20,698-0000
37' WNW
C SW SW Sec. 20 Twp. 21 S, Rg. 33. West
660 Ft. from South Line of Section
4657 Ft. from East Line of Section

OPERATOR: License # 5476
Name DNB Drilling, Inc.
Address 535 N. Oliver
City/State/Zip Wichita, KS 67208
Contact Person Jim Donelson
Phone (316) 687-5471

(Note: Locate well on Section Plat on reverse side)
Nearest lease or unit boundary line 660 feet
County Finney

CONTRACTOR: License # 5382
Name Cheyenne Drilling, Inc.
City/State Garden City, KS

Lease Name Savolt Well # 1-A
Ground surface elevation 2925 feet MSL
Domestic well within 330 feet: yes X no

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj X Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Municipal well within one mile: yes X no
Depth to bottom of fresh water 175
Depth to bottom of usable water 1100
Surface pipe by Alternate: 1 2 X

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

Surface pipe planned to be set 300!
Conductor pipe required
Projected Total Depth 4650 feet
Formation St. Louis

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date 1-28-87 Signature of Operator or Agent Title Office Manager

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 300 feet per Alt.
This Authorization Expires 2-29-87 Approved By 1-29-87

SPUD 1-28-87 P.A.L.

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ Same as previous intent feet depth with sx's of
2nd plug @ feet depth with sx's of
3rd plug @ feet depth with sx's of
4th plug @ feet depth with sx's of
5th plug @ feet depth with sx's of
(2) Rathole with sx's (b) Mousehole with sx's

PUSHER Jacob T. ...
TD 4790 FORMATION MIX
SURFACE PIPE 8 3/8 @ 433
ANEHYDRITE 2040 ELEVATION 2925
STARTING TIME & DATE 1:00 AM - 2-6-87
COMPLETION TIME & DATE 4:20 AM
1st PLUG @ 2040 FT. W/ 5" SX
2nd PLUG @ 1120 FT. W/ 8" SX
3rd PLUG @ 460 FT. W/ 5" SX
4th PLUG @ 40-0 FT. W/ 1" SX
RAT HOLE CIRCULATED W/ 15" SX
MOUSE HOLE CIRCULATED W/ SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY 2nd Generation
TECHNICIAN R.A.J. ... 60/40 n/s 70" ...

STATE CORPORATION COMMISSION
FEB 9 1987
CONSERVATION DIVISION
Wichita, Kansas