

1 050718

API NUMBER 15- Comp. 1-2-79

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SW _____, SEC. 15, T 21 S, R 33 WWE

1320 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5506

Lease Name Morris A Well # 1

Operator: Woolsey Petroleum Corp.

County Finney

Name & Address 300 West Douglas, Suite 400

Well Total Depth 2800 91.00 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 366

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:45 pm Day: 11 Month: December Year: 19 85

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 2764' PBTD 2739' Perfs at 2995-2606' Top of cement 1470'

1st plug pump 20 sx cement to bottom and stop plug at 2000'

2nd plug squeeze well with 3 sx hulls, 5 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Richard W. Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Clyde Wiley observed the plugging

Operations Completed: Hour: 1:30 pm Day: 11 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement to bottom and stopped plug at 2000'

2nd plug squeezed well with 3 sx hulls, 5 sx gel, 70 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pumped 125 sx cement.

Maximum pressure 700 psi and shut in 200 psi

Remarks: Recovered 1330' 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

Clyde Wiley observe this plugging. 12-20-85

INVOICE

DATE DEC 20 1985

INV. NO. 11688

Signed Richard W. Lacey (TECHNICIAN)

DEC 20 1985

12-20-85