

1080333

TO: STATE CORPORATION COMMISSION

API NUMBER 15-055-20,155-0000
SE SW SEC. 30, T 21 S, R 33 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3300 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME VEDA LOOMIS WELL # 2

TECHNICIAN'S PLUGGING REPORT 8/28

COUNTY FINNEY 156.10

OPERATOR LICENSE # 32550

WELL TOTAL DEPTH 4803 FEET

OPERATOR: ST. JOHNS OPERATING #1 L.P. PRODUCTION CSG: SIZE 5 1/2" @ 4802' WITH 125 SX

NAME AND 16800 GREENSPPOINT PARK DR.#380-S SURFACE CASING: SIZE 8 5/8" @ 519' WITH 530 SX

ADDRESS HOUSTON, TX 77060

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT AND HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 9:45 AM DAY: 28 MONTH: 08 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT AND HORTON PLUGGING (PHONE) 580-854-6515

WERE: DV @ 2802' W/250 SX CEMENT. PERFS AT 4328-4756. CASING LEAK AT 2998'. SQUEEZED W/125SX SET CIBP @ 4210'. 1ST PLUG AT 700' WITH 50 SX CEMENT. 2ND PLUG AT 525' WITH 40 SX CEMENT. 3RD PLUG AT 0-40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:00 PM DAY: 28 MONTH: 08 YEAR: 2000

ACTUAL PLUGGING REPORT

CIBP @ 4210'. TUBING IN HOLE. LOADED CASING WITH MUD. PULLED TUBING OUT OF HOLE. LOADED HOLE WITH MUD. PUMPED 50 SX CEMENT AT 700'. WELL WAS CIRCULATING. PULLED CASING TO 525' PUMPED 40 SX CEMENT. DISPLACED WITH MUD. CIRCULATING TO SURFACE WITH MUD. PULLED CASING TO 40' PUMPED 10 SX CEMENT.

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 712' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED
DATE 9/11/00 SIGNED Kevin D. Strube (TECHNICIAN) FORM CP-2/3
2001060635

RECEIVED
STATE CORPORATION COMMISSION
9-6-00
SEP 06 2000
CONSERVATION DIVISION
Wichita, Kansas