

1 090284

5-7

15.055.00158-0000

API NUMBER 15- Drill Completion Date 3/3/61

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

App. C NW , SEC. 20 , T. 21 S, R 32 W/E

App. 3960 feet from S section line

App. 3960 feet from E section line

Lease Name Greathouse Well # 1-20

County Finney 89.31

Well Total Depth 2750 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 293

TECHNICIAN'S PLUGGING REPORT

Operator License # 3871

Operator: Hugoton Energy Corporation

Name &

Address 229 E. William, Ste. 500

Wichita, KS 67202

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67530

Company to plug at: Hour: 9:20 a.m. Day: 7 Month: 5 Year: 1993

Plugging proposal received from Manny Boatright

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 2745' w/300 sx cement, Perfs at 2656-66'

1st plug set CIBP at 2600' w/2 sx cement on top,

2nd plug shoot at 1150' and pump 80 sx cement,

3rd plug spot 50' sx cement at 330',

4th plug spot 10 sx cement at 40'.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12 p.m. Day: 7 Month: 5 Year: 1993

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2600' w/2 sx cement on top,

2nd plug pulled to 1100' and spotted 80 sx cement,

3rd plug pulled to 330' and spotted 50 sx cement,

4th plug pulled to 40' and spotted 10 sx cement.

Circulated cement to cellar.

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAY 12 1993  
CONSERVATION DIVISION  
WICHITA, KS

5-12-93

Remarks: Used 60/40 Pozmix 6% gel by Western. Recovered 1139' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
observe this plugging.

DATE 5-18-93

Signed [Signature] (TECHNICIAN)

INV. NO. 37741