

To: 1 080110 3-11
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 055-20,206-0000

C SW, SEC. C12, T 21 S, R 32 W/4
1320 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4058

Lease Name Brakey Well # 1

Operator: American Warrior, Inc.

County Finney 88.56

Name & Address P.O. Box 399

Well Total Depth 2725 feet

Garden City, KS 67846

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well Gas Well X Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Mikes Testing & Salvage, Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524-0209

Company to plug at: Hour: 1 p.m. Day: 10 Month: 3 Year: 19 - 97

Plugging proposal received from Kevin Wiles

(company name) American Warrior, Inc. (phone) 316-275-2963

Work: 4 1/2" at 2713' w/550 sx cement, PBD 2713', Open hole 2713-25', Had casing leak 5' below slips

1st plug pump 20 sx cement and hulls on bottom,

2nd plug at 1400' with 80 sx cement, 3rd plug at 700' with 40 sx cement,

4th plug at 360' with 40 sx cement,

5th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:30 a.m. Day: 11 Month: 3 Year: 1997

ACTUAL PLUGGING REPORT 1st plug pumped 300 lbs. hulls and 20 sx cement. Maximum pressure

700 psi. Top of cement 2200'. Shot casing at 1400'. Casing leak at approx. 300'

Ran tubing to 320', pressured up to 1000#.

2nd plug ran tubing to 1400' and spotted 20 sx cement,

3rd plug pulled up to 930' and circulated clean. Pulled tubing, shot casing at 706', still not free. 4th plug shot at 600' and pumped 30 sx cement, 5th plug pulled to 350' and pumped 40 sx cement, 6th plug topped off with 15 sx cement.

Remarks: Used 65/35 Pozmix 6% gel by Halliburton. Recovered 600' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
DATE MAR 21 1997
Wichita State Office observe this plugging.

Signed Kevin D. Stube (TECHNICIAN)

INV. NO. 47778