

To: 1 080109 3-11
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 055-20,208-0000
C NW , SEC. 13 , T 21 S, R 32 W/E
3960 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License / 4058
Operator: American Warrior, Inc.
Name & Address: P.O. Box 399
Garden City, KS 67846

Lease Name Rayl Trust Well # 1
County Finney 88.40
Well Total Depth 2720 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 352

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 11 Month: 3 Year: 19 97
Plugging proposal received from Kevin Wiles
(company name) American Warrior, Inc. (phone) 316-275-2963

Work: 4 1/2" at 2720' w/550 sx cement, Perfs at 2705-2713'
1st plug pump 100 sx cement and 200 lbs. hulls to bottom,
2nd plug pump 30 sx cement on stub,
3rd plug pump 40 sx cement at 380',
4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 6 p.m. Day: 11 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug loaded hole with water, pumped 50 bbl.; pumped 100 sx cement with 200 lbs. hulls mixed in, displaced to 1000'. Maximum pressure 500 psi
2nd plug shot casing at 560' and pumped 30 sx cement,
3rd plug pulled up to 380' and pumped 40 sx cement,
4th plug pulled out of hole and topped off with 10 sx cement.

Remarks: Used 65/35 Pozmix 6% gel by Halliburton. Recovered 560' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE MAR 21 1997
INV. NO. 47780
3-11

Signed Kevin P. Strube (TECHNICIAN)

KANSAS RECEIVED
CORP COM
MAR 20 11:39 AM