

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. 105-6LOCATION NE-NE-SESEC. 9 TWP. 22 RGE. 13-4Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Kelley "A"Operator Shelley Oil Co Address Box #391 Hutchinson-Kans.Field _____ County StaffordTotal Depth 3784 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 448 ft. Circulated with cement.
5 1/2" casing set at 3779 ft. - 125 sacks of cement.
Lower wellbore plugged at 3584 ft. - Chert from 3584 ft. to 3450 ft.
dumped 5 sacks of cement at 3450 ft. - kicked off &
hulled the 5 1/2" casing - mud to 250 ft. - Set Rock Bridge
& 15 sacks of cement at 250 ft. - mud to 35 ft. - Plug
& 10 sacks of cement at the surface.
Shull Casing Pulling Co. - Plugging Contractor

RECEIVED
 STATE CORPORATION COMMISSION

9-22-51

PLUGGING
 SEP 22 1951
 CONSERVATION DIVISION
 STATE CORPORATION COMMISSION
 WICHITA, KANSAS
 FILE SEC. 9 TWP. 22 RGE. 13-4
 BOOK PAGE 105 LINE 6

C. H. Stough
 District Conservation Agent

Date 9-19-51