

APCP

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

1-28-64

RECEIVED
STATE CORPORATION COMMISSION
JAN 28 1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pan American Petroleum Corporation

Complete Address: Box 432, Liberal, Kansas

Lease Name F. H. Mellies Well No. # 4

Location C E/2 ^{NW NE} ~~SE NW~~ Sec. 1 Twp. 22 Rge. 12 (E) (W)W

County Stafford Total Depth 3598'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 4:00 PM Day 27th Month Jan. Year 1966

The Above well was plugged as follows:

594' of 8 5/8" surface pipe, cemented with 300 sacks. 3595' of 5 1/2" long
string, cemented with 150 sacks. Plug back to 3540'. Top perferation 3299'.
Bottom of the hole was sanded to 3252', and cemented with 5 sacks, through
the dump bailer. 2692' of 5 1/2" long string was recovered from the hole. Fluid
in the hole was at 370', bridge plug and rock bridge from 370' to 336'. Hole
was filled with 4 yards of ready-mix cement from 336' to 33', and 10 sacks
of cement from 33' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1-28-66

INV. NO. 2659-W