

15.185-01958-0001

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

1-26-66

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 26 1966

CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Pan American Petroleum Corporation

Complete Address: P. O. Box 432, Liberal, Kansas

Lease Name F. H. Mellies Well No. # 1

Location C W/2 NW NE Sec. 1 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3651'

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 12:00PM Day 21st Month Jan. Year 1966

The Above well was plugged as follows:

277' of 8 5/8" surface pipe, cemented with 150 sacks. 3646' of 4 1/2" long
string, cemented with 125 sacks. Plug abck to 3378'. Top perferation 3299'.
Hole bottomed at 3287, and cemented with 3 sacks, through the dump bailer
at 3287'. 30' of 4 1/2" long string was recovered from the hole. Fluid level
in the hole was now at 400'. 6 yards of ready-mix cement was dumped on fluid
at 400', and filled to 30' from the base of the cellar. Hole was capped with
10 sacks of cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/26/66
INV. NO. 2655-W

Signed: Aubie Elving
Well Plugging Supervisor