

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. NW SE NE

LOCATION NW SE NE

SEC. 1 TWP. 22 RGE. 12

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Melvin "A"

Operator Petroleum, Inc. Address 314 Rocky Bldg - Wichita - Kansas

Field \_\_\_\_\_ County Stafford

Total Depth 3612 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 250 ft - Circulated with cement.  
5 1/2" casing set at 3584 ft. Plugged back from bottom  
to 3285 ft with mud & chat - 10 sacks of cement pumped  
in the 5 1/2" casing at 3285 ft. Shot off & pulled the 5 1/2" casing.  
Filled with mud to 250 ft - Back Bridge & 15 sacks  
of cement at 250 ft - Mud to 30 ft - Bridge &  
10 sacks of cement at the surface

3-23-50

**PLUGGING**  
FILE SEC. 1 T. 22 R. 12  
BOOK 144 LINE 17  
STATE CORPORATION  
COMMISSION  
KANSAS

E. W. Stough  
District Conservation Agent  
Date 3-17-50