

15-185-01955.0000

Form CP-3
Rev. 6-26-62

Yp
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1965

CONSERVATION DIVISION
Wichita, Kansas
5-24-65

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Mollies Well No. # 1

Location C W/2 NE NE Sec. 1 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3555'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 10:30AM Day 22nd Month May Year 1965

The Above well was plugged as follows:

250' of 8 5/8" surface pipe, cemented with 175 sacks. 3550' of 5 1/2" long
string, cemented with 150 sacks. Top perferation 3277'. Plug was pushed
to 3275', and 25' of sand, and cemented with 5 sacks. 2410' of 5 1/2" long
string was recovered from the hole. Fluid level was up in the hole.
Bridge plug was pushed in fluid to 255', and 10' of rock and sand. 5
sacks of cement was mixed in barrel, and put on plug at 245', through
the dump bailer, and let set over-night. Next morning hole was bailed
dry, and 20 sacks of cement was added to the plug. Hole was filled with
mud to 40', and 10' of rock bridge, and cemented with 10 sacks to the base
of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/24/65
INV. NO. 1206-W