

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 30 1967

3-30-67

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued February 28, 1967.

Operator's Full Name Pan American Petroleum Corporation

Complete Address: P. O. Box 432, Liberal, Kansas

Lease Name F. H. Mellies Well No. # 3

Location C E/2 NW NE Sec. 1 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3566'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 1:30PM Day 25th Month March Year 1967

The Above well was plugged as follows:

586' of 8 5/8" surface pipe, cemented with 500 sacks. 3564' of 5 1/2" long
string, cemented with 100 sacks. This is an open hole. Bottom of the hole
was sanded to 3550', and cemented with 5 sacks, through the dump bailer.
2840' of 5 1/2" long string was recovered from the hole. Fluid in the hole
was bailed down to 450', bridge plug and rock bridge from 450' to 440',
and cemented with 25 sacks. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/30/67

INV. NO. 4979-W

Signed: Audie Elving
Well Plugging Supervisor