

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

8-14-67

RECEIVED  
STATE CORPORATION COMMISSION

AUG 14 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Intent to Drill,  
filed August 4, 1967.

Operator's Full Name Petroleum, Inc.

Complete Address 300 W. Douglas, Wichita, Kansas 67202

Lease Name Helmerts Well No. # B-1

Location NW SE SE Sec. 1 Twp. 22 Rge. 12 (E) (W) W

County Stafford Total Depth 3220'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Garvey Drilling Company

Address R. R. # 2, Great Bend, Kansas 67530 License No.       

Operation Completed: Hour 10:15 P.M. Day 9th Month August Year 1967

The above well was plugged as follows:

254' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid level  
in the hole was at 170'. 1st cementing plug, and 1/2 sack of hulls was pushed  
in fluid to 240', and cemented with 25 sacks, through the drill pipe, with  
cement from 240' to 165'. Hole was filled with mud to 40', 2nd cementing  
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid at 40',  
and cemented with 9 sacks, with cement from 30' to the base of the cellar.  
Rat and mouse holes bridged and cemented with 4 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving  
Well Plugging Supervisor

DATE 8/14/67

INV. NO. 6134-W