

KANSAS



STATE CORPORATION COMMISSION

15-055-20006-0000

CONSERVATION DIVISION AGENT'S REPORT

10-21-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
OCT 21 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pan American Petroleum Corporation

Complete Address: Box 432, Liberal, Kansas

Lease Name F. Finnup Well No. 1

Location NE NW Sec. 3 Twp. 23 Rge. 33 (E) (W)

County Finney Total Depth 4900'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: None

Plugging Contractor: Sargents Casing Pulling Co.

Address: Box 506, Liberal, Kansas License No. 511

Operation Completed: Hour 4:00pm Day 17 Month 10 Year 1968

The Above well was plugged as follows:

8 5/8" to 568' circulated w/cement. 4 1/2" to 4855' cemented.

Top perforations 3790' Plug bottom w/ 20 sacks cement.

Top of cement 3494' Mud 3494' to 550'

Spotted 35 sacks cement 550' to 450' Mud 450' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'. Company Pump

Pulled 1519' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Edgar J. Eves
Well Plugging Supervisor

DATE 10/21/68
INV. NO. 8668-44