

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

MAR 28 1966  
3-28-64  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Alpine Oil & Royalty Company 15185-30733-0000

Complete Address: 800 Bitting Bldg., Wichita, Kansas

Lease Name A. L. Smith Well No. # 1

Location SE NE NW Sec. 2 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 3740'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Gabbert-Jones, Inc.

Address: 514 Orpheum Bldg., Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 5:00PM Day 23rd Month March Year 1966

The Above well was plugged as follows:

245' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fluid level in the hole was at 60'. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to 225', and cemented with 25 sacks, through the drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged solid with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2-28-66

INV. NO. 2931-W

Signed: Archie Elving  
Well Plugging Supervisor