



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 2 - 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Galaxy Oil Compy

Complete Address 918 Lamar Street, Wichita, Falls, Texas 76301

Lease Name Beymer Well No. 1

Location C NE NE Sec. 22 Twp. 21 Rge. 37 (EX) (W)

County Kearny Total Depth 2775'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated _____

Plugging Contractor Dowell Cementing Co.

Address Ulysses, Kansas License No. _____

Operation Completed: Hour 8:00PM Day 22 Month 3 Year 1974

The above well was plugged as follows:

10 3/4" to 329' circulated w/ cement. 7" to 2652' cemented.

No Perforations, Open Hole 2652' to 2775'

Plug bottom w/7" Bridge Plug set at 1200' w/ 68 of cement on top of plug.

Mud 1194' to 600' Spotted 150 sacks cement 600' to 300'

Mud 300' to 10' Bridge & 5 sacks cement 10' to 0'.

Pulled 635' of 7" casing. Dowell Cementing Pump Truck.

Bill Nichols had plugging authority and supervised Plugging

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Lewis
Well Plugging Supervisor

DATE 4/2/74

INV. NO. 8861-W

INVOICED