

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
DEC 19 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Abercrombie Drilling Inc.

Complete Address 801 Union Center, Wichita, Kansas 67202

Lease Name Pfeiffer Well No. 1

Location C N/2 SW Sec. 9 Twp. 21 Rge. 35 (E) (W)

County Kearny Total Depth 5030'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated None

Plugging Contractor Southwest Casing Pulling Co.

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 1:00PM Day 13 Month 12 Year 1972

The above well was plugged as follows:

8 5/8" to 365' circulated w/ cement. 5 1/2" to 4704' cemented.

Top perforations 4470' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4400' Mud 4400' to 700'

Spotted 30 sacks cement 700' to 550' Mud 550' to 350'

Spotted 40 sacks cement 350' to 250' Mud 250' to 45'

Plug, Halls & 15 sacks cement 45' to 0'. Sun cementing Pump Truck.

Pulled 2500' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edmond J. Eves
Well Plugging Supervisor

INVOICED

DATE 12/19/72

INV. NO. 6740-u