

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION C off NE NE

SEC. 27 TWP. 21 RGE. 34w

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease Nunn

Operator Shallow Water Ref. Co. Address Ward Parkway Bank Bldg. Kansas City Mo.

Field Nunn County Finney

Total Depth 4754 Feet.

(Describe briefly the manner in which the well was plugged)

Filled hole with sand to 4610'. Dumped two sacks cement to 4596'. Ran 320 gal. sand to 4260'. Dumped three sacks cement to 4245'. Bailed fluid from 160' to 290'. Rock bridge set at 270'. Dumped 30 sacks cement to 247'. Mud to 308 from top. Rock bridge to 20'. Dumped 10 sacks cement to 6' below surface. Cut off pipe and capped.

Recovered 935' of 5 1/2"'.

6-25-56

IVED
ION COMMISSION

London E. Jar
District Conservation Agent

Date 6-22-56

PLUGGING
FILE SEC. 27 T. 21 R. 34w
BOOK PAGE 61 LINE 13

JUN 25 1956
WICHITA, KANSAS