

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 70-38LOCATION S-SW-NESEC. 34 TWP. 11 RGE. 34-WDry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 8 Lease Hoffman - "K"Operator The Shallow Water Refining Co. Address Garden City - Kansas -Field _____ County FinneyTotal Depth 4720 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe - 2 1/2" - 277 ft. Circulated with cement -
5% casing set at 4683 ft. Cemented with 125 sacks cement.
Plugged back to 4290 ft with mud - Sand Wells Plug
& Chat - Dumped 5 sacks of cement at 4290 ft - Shot off &
grilled the 5% casing - mud to 277 ft - Set Rock Bridge
& 15 sacks of cement at 277 ft - Mud to 30 ft - Plug
& 10 sacks of cement at the surface -
A & L Pipe Pulling Co - Plugging Contractors

STATE CORPORATION COMMISSION

APR 21 1951 4-21-51

CONSERVATION DIVISION

District Conservation Agent

Date 4-15-51

PLUGGING
FILE SEC 34-T-21-R34-W
BOOK PAGE 79 LINE 38