

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
 Administrator
 P. O. Box 17027
 Wichita, Kansas 67217

RECEIVED
 STATE CORPORATION COMMISSION

NOV 15 1972

CONSERVATION DIVISION
 Wichita, Kansas

Operator's Full Name Kansas Nebraska Nat Gas Co. Inc.
 Complete Address Box 608, Hastings, Nebraska 68901
 Lease Name Martin Well No. 1
 Location App C E/2 W/2 Sec. 23 Twp. 21 Rge. 41 (E) (W)
 County Hamilton Total Depth 2795'
 Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____
 Other well as hereafter indicated _____
 Plugging Contractor Sargents Casing Pulling Co.
 Address Box 506, Liberal, Kansas License No. 511
 Operation Completed: Hour 2:00PM Day 11 Month 11 Year 1972

The above well was plugged as follows:

7" to 365' circulated w/ cement. 4 1/2" to 2795' cemented.
Top perforations 2778' Plug bottom w/ 15 sacks cement.
Top of cement 2595' Mud 2595' to 600'
Spotted 30 sacks cement 600' to 500' Mud 500' to 425'
Spotted 30 sacks cement 425' to 300' Mud 300' to 45'
Plug, Hulls & 10 sacks cement 45' to 0'. Company Pump
Pulled 1824' of 4 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edward J. Eves
 Well Plugging Supervisor

INVOICED

DATE 11/15/72
 INV. NO. 6635-11