

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-043 - 20,704-0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Amoco Production Co.

Complete Address PO Box 432, Liberal Kans.

Lease Name Sills Well No. 1

Location 1980 FSL-660FEH-5E1/4 Sec. 33 Twp. 21 Rge. 35 (East) (~~West~~)

County Kearny Total Depth 5000

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated never produced.

Plugging Contractor Midwest Casing Pulling

Address Sublette Kans License No. 711

Operation Completed: Hour: 7:00 PM Day: 12 Month: June Year: 1981

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

There was 1602' of 8 1/2" surface casing
5 1/2" was set to 4999'. Perforations were
4514-4506. Cast Iron bridge plug at 4490'
with 5 lbs cement on top. 1st plug set
at 1600' with 60 lbs cement. 2nd plug at
700' with 30 lbs cement. 3rd plug at 400'
with 10 lbs cement.

There was 2053' of 5 1/2" salvaged.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7-27-81

INV. NO. 6058-W

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1981

CONSERVATION DIVISION
Wichita, Kansas

Signed: Therese Thomas
Conservation Division Agent

6-16-81