

R

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 06 1978
CONSERVATION DIVISION
Wichita, Kansas
2-6-78

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Brownie Olson

Complete Address Box 981, Great Bend, Kansas 67530

Lease Name Jackson Well No. 1

Location 300' W of SW NE Sec. 20 Twp. 21 Rge. (E) (W) 25

County Hodgeman Total Depth 4460'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698, Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 3:45 PM Day H Month 2 Year 1978

The above well was plugged as follows:

Total Depth 4460' 8 5/8 csg set 246' cwc 225 sk.

5 1/2 csg set 4459' cw 125 sk.

Filled 5 1/2 csg W/sd (4460'-4450') Dumped 5 sk cmt W/dump bailer. (4450'-4415')

Cutoff & recovered App 3000' of 5 1/2 csg.

Pumped down 8 5/8 csg with 22 sk gel & water.

Set 70 sk cmt plug at 600' thru tbg.

Circulated 80 sk cmt 240' to base of cellar thru tbg.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2-8-78

INV. NO. 6726-W

Signed: [Signature]
Well Plugging Supervisor