

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 13 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Eldorado Supply CompanyComplete Address: 764 Oil Hill Road, El Dorado, Kansas 67042Lease Name Lee "S" Well No. 2Location C SW NW Sec. 26 Twp. 21 Rge. 25 (E) (W)County Hodgeman Total Depth 4579'Abandoned Oil Well X Gas Well  Input Well  SWD Well  D & A XOther well as hereafter indicated: NonePlugging Contractor: Southwest Casing PullingAddress: Box 364, Great Bend, Kansas License No. 399Operation Completed: Hour 2:30PM Day 11 Month 9 Year 1968

The Above well was plugged as follows:

8 5/8" to 258' circulated w/ cement. 5 1/2" to 4555' cemented.No Perforations, 24' of open Hole. Plug bottom w/ sand & 5 sks. cement.Top of cement 4500' Mud 4500' to 800'Spotted 100 sacks cement 800' to 450' Mud 450' to 250'Spotted 30 sacks cement 250' to 160' Mud 160' to 30'Plug, Hulls & 10 sacks cement 30' to 0'. Allied Pump Company.Pulled 2705' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Green  
Well Plugging Supervisor

INVOICED

DATE 9/13/68INV. NO. 8455-W