

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 3 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

5-3-71  
15-185-20337-0000

Operator's Full Name Petroleum Inc.  
Complete Address Rt. 2 Great Bend, Ks  
Lease Name Beaver B Well No. 1  
Location NE/SE/SW Sec. 9 Twp. 23 Rge. 14 (E) (W) W  
County Stafford Total Depth 4014  
Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Santa Fe Pipe & Supply Inc.  
Address Box 562 Great Bend, Ks License No. 574  
Operation Completed: Hour 11:00 AM Day 1 Month 5 Year 1971

The above well was plugged as follows:

250 ft of 8 5/8 surface pipe cemented with 250 sacks. 4013 ft of 5 1/2  
long string cemented with 150 sacks. Top perf. 3962-70 ft. Sand  
back to 3950 ft, 5 sacks cement with bailer. Pulled 1916 ft of 5 1/2.  
Pumped 2 sacks hulls, 15 sacks gel. & 100 sacks cement to surface.  
Globe Cementing Co. Great Bend, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. Russell Biberstein  
Well Plugging Supervisor

DATE 5/3/71  
INV. NO. 3637-11