

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 21 1965

CONSERVATION DIVISION  
Wichita, Kansas

5-21-65

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Texaco Inc. 15-185-60007-0000

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name T. A. Malin Well No. # 1

Location SE SE SE Sec. 13 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 3782'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 3:15 PM Day 20th Month May Year 1965

The Above well was plugged as follows:

820' of 10 3/4" surface pipe, cemented with 625 sacks. 3699' of 7"  
long string, cemented with 85 sacks. Plug back to 3682'. Top perferation  
3630'. Bottom of the hole was sanded to 3600', and cemented with 5 sacks.  
2000' of 7" long string was recovered from the hole. Hole was filled  
with mud to 300', and 10' of rock bridge, and cemented with 30 sacks.  
Hole was filled with mud to 40', and 10' of rock bridge, and cemented  
with 15 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 5/21/65

INV. NO. 1195-11