

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

4-7-65  
RECEIVED  
STATE CORPORATION COMMISSION  
APR 7 1965  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Texaco Inc. 15-185-11836-0000

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name T. A. Malin Well No. # 3

Location NW SE SE Sec. 13 Twp. 23 Rge. 14 (E) (W) W

County Stafford Total Depth 3787'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 12:30PM Day 5th Month April Year 1965

The Above well was plugged as follows:

833' of 10 3/4" surface pipe, cemented with 600 sacks. 3780' of 7"  
long string, cemented with 100 sacks. Plug back to 3625'. Top perf-  
eration 3556'. Bottom of the hole was sanded to 3540', and cemented  
with 5 sacks. Pipe parted and 1800' of 7" long string was recovered  
from the hole. Hole was filled with mud to 280', and 15' of rock  
bridge, and cemented with 35 sacks. Hole was filled with mud to 40',  
and 10' of rock bridge, and cemented with 15 sacks to the base of  
the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 4/7/65

INV. NO. 942-W

The March 17th Well Plugging  
Authority, gave this well in  
Barton County. This is in er-  
ror, it should have been Sta-  
fford County

Archie Elving

15-185-11836-0000