

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

4-26-65

APR 26 1965

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Texaco Inc. 15-185-10942-0000

Complete Address: 614 Bitting Bldg., Wichita, Kansas

Lease Name T. A. Malin Well No. # 2

Location NE SE SE Sec. 13 Twp. 23 Rge. 14 (E) (W)W

County Stafford Total Depth 4076'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 10:45AM Day 23rd Month April Year 1965

The Above well was plugged as follows:

828' of 10 3/4" surface pipe, cemented with 650 sacks. 4054' of 7" long  
string, cemented with 750 sacks. Plug back to 3993'. Top perforation  
3536'. Bottom of the hole was sanded to 3500', and cemented with 5 sacks.  
1400' of 7" long string was recovered from the hole. Hole was filled  
with mud to 275', and 10' of rock bridge, and cemented with 30 sacks.  
Hole was filled with mud to 40', and 10' of rock bridge, and cemented  
with 15 sacks to the base of the cellar.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 4/26/65  
INV. NO. 1053-W

Signed: Archie Elving  
Well Plugging Supervisor

On the March 17th Well Plugging Authority, it gave this well in Barton County, this is in error. It should have been Stafford County

*Archie Elving*  
Archie Elving

15-185-10942-0000