


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 30 Twp. 21S Rge. 24W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW SW
Lease Owner Jack Bowles
Lease Name Wright Well No. #1-A
Office Address 401 Local Federal Bldg., Okla. City, Okla. 73102
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11/6/75 19
Application for plugging filed 11/6/75 19
Application for plugging approved 11/6/75 19
Plugging commenced 11/6/75 19
Plugging completed 11/6/75 19
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well: 4600 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	361'	8 5/8"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged through drill pipe @ 550' w/50 sacks cement.
Plugged through drill pipe @ 250' w/25 sacks cement.
Plugged through drill pipe @ 40' w/10 sacks cement.

11-10-75

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.
Address 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson
905 Century Plaza, Wichita, Ka. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of November, 19 75

My commission expires _____

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard
Marilyn Sinard Notary Public.

~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~
~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~
~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~

WRIGHT #1A
NW SW Sec. 30-21S-24W
Hodgeman County, Kansas

CONTRACTOR: Chief Drilling Co., Inc.
CASING RECORD: Ran (9 Jts.) 355' used 8 5/8", set
@ 361', cemented w/ 225 sacks 2% gel,
3% c.c.

COMMENCED: 10/27/75
COMPLETED: 11/6/75

FORMATION	FROM	TO	ELEVATIONS
Surface Gravel	0	364	2390' Gr.
Sand, Shale & Clay	364	1069	2393' D.F.
Shale & Sand	1069	1612	2395' K.B.
Shale	1612	2086	
Lime	2086	2299	
Shale & Lime	2299	2560	
Lime	2560	2625	
Shale & Shells & Lime	2625	2760	
Lime & Shale	2760	2893	
Lime	2893	4600	
RTD	4600 D & A.		

FORMATION TOPS

Anhydrite	1608 +	787
Base Anhy.	1644 +	751

RECORDED
OCT 31 1975
COMMISSIONER

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the NW SW of Section 30-21S-24W,
Hodgeman County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.
Jim Robinson
Jim Robinson, Vice-President

Subscribed and sworn to before me this 6th day of November, 1975 .

MARILYN SINARD
STATE NOTARY PUBLIC
SEDGWICK COUNTY, KANSAS
MY COMM. EXP. APR. 30, 1979

Marilyn Sinard
Marilyn Sinard, Notary Public