

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-083-20,175-0000

LEASE NAME Beiber "A"

WELL NUMBER #1 SWD

SPOT LOCATION 150' W of C SW NE

SEC. 30 TWP. 21 SRGE. 24 (E) or (W)

COUNTY Hodgeman

Date Well Completed 9-1-71

Plugging Commenced 7-11-86

Plugging Completed 7-11-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS 970 Fourth Financial Center, Wichita, KS 67202

PHONE # (316) 265-3311 OPERATORS LICENSE NO. 5245

Character of Well SWD
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? NA If not, is well log attached? YES

Producing formation Cedar Hills Depth to top 1200' bottom 1350' T.D. 1420'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Cedar Hills	Water	1200'	1350'	8-5/8"	500'	None
				5-1/2"	1414'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Pump 150# hulls down casing.

Set 70 sx cmt plug from from 500' to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245

Address 970 Fourth Financial Center, Wichita, KS 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.

Melvyn D. Abels

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Melvyn D. Abels



RECEIVED 970 Fourth Financial Ctr.
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me, Notary Public, on this 21 day of July, 1986

Amy R. Blecha
Notary Public

My Commission expires: July 16, 1990

JUL 22 1986

Form CP-4 1-84
Revised 05-83

DRILLERS LOG#1 Bieber "A"

CASING RECORD: 500.17' of new 8-5/8" surface casing. COMPANY: Oicmar Oil Company DESCRIPTION: 150' West C/SW NE
 CONTRACTOR: Strata Drilling, Inc. Section 30-21S-24W
 Hodgeman County, Kansas
 TOTAL DEPTH: 4585' COMMENCED: August 23, 1971
 COMPLETED: September 1, 1971

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Post Rock, Shale & Sand	0	525	Ran 500.17' of new 8-5/8" surface casing; set and cemented at 506.17' with 225 sacks of regular cement, 2% gel and 3% C. C. Plug down at 1:50 A. M. August 24, 1971.
Shale w/Sand Streaks	525	725	
Red Bed & Shale	725	968	
#1 Anhydrite	968	1000	
Red Bed & Shale	1000	1071	
Dakota Sand	1071	1294	
Red Bed & Shale	1294	1568	
Shale	1568	1591	
#2 Anhydrite	1591	1627	
Shale	1627	2053	
Shale & Shells	2053	2235	
Shells, Shale & Lime	2235	2442	
Shale & Lime	2442	3396	
Lime w/Shale Streaks	3396	3596	
Shale & Lime	3596	4420	Dry.
Lime	4420	4490	
Cherty Lime	4490	4513	
Lime	4513	4523	
Lime & Shale	4523	4585	Making a salt water disposal well out of above.

Rotary Total Depth 4585'

5 1/2" casing set and cemented at 1414' with 370 cubic feet Halliburton light cement. Plug down at 4:30 A. M. September 1, 1971.

STATE OF KANSAS)
) ss.
 COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
 Charles W. Steincamp, President

Subscribed and sworn to before me this 2nd day of September, 1971.

My Commission Expires:

December 14, 1973

RECEIVED
 STATE CORPORATION COMMISSION

MAY 30 1986

CONSERVATION DIVISION
 Wichita Kansas

Elaine H. Taylor
 Elaine H. Taylor, Notary Public

D R I L L E R S L O G#1 Bieber "A"

CASING RECORD: 500.17' of new 8-5/8" surface casing. COMPANY: Okmar Oil Company DESCRIPTION: 150' West C/SW NE
 CONTRACTOR: Strata Drilling, Inc. Section 30-21S-24W
 Hodgeman County, Kansas
 TOTAL DEPTH: 4585' COMMENCED: August 23, 1971
 COMPLETED: September 1, 1971

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Post Rock, Shale & Sand	0	525	Ran 500.17' of new 8-5/8" surface casing; set and cemented at 506.17' with 225 sacks of regular cement, 2% gel and 3% C. C. Plug down at 1:50 A. M. August 24, 1971.
Shale w/Sand Streaks	525	725	
Red Bed & Shale	725	968	
#1 Anhydrite	968	1000	
Red Bed & Shale	1000	1071	
Dakota Sand	1071	1294	
Red Bed & Shale	1294	1568	
Shale	1568	1591	
#2 Anhydrite	1591	1627	
Shale	1627	2053	
Shale & Shells	2053	2235	
Shells, Shale & Lime	2235	2442	
Shale & Lime	2442	3396	
Lime w/Shale Streaks	3396	3596	
Shale & Lime	3596	4420	
Lime	4420	4490	Dry.
Cherty Lime	4490	4513	Making a salt water disposal well out of above.
Lime	4513	4523	
Lime & Shale	4523	4585	

Rotary Total Depth 4585'

5½" casing set and cemented at 1414' with 370 cubic feet Halliburton light cement. Plug down at 4:30 A. M. September 1, 1971.

STATE OF KANSAS)
) ss.
 COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
 Charles W. Steincamp, President

Subscribed and sworn to before me this 2nd day of September, 1971.

My Commission Expires:

December 14, 1973

RECEIVED
 STATE CORPORATION COMMISSION
 CONS. DIV. WICHITA, KS
Elaine H. Taylor
 Elaine H. Taylor, Notary Public

JUL 22 1986