

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-083-20,164-0000

LEASE NAME Bieber

WELL NUMBER #1

SPOT LOCATION C SW SE

SEC. 30 TWP. 21 SRGE. 24 ~~(N)~~ or (W)

COUNTY Hodgeman

Date Well Completed 6-24-71

Plugging Commenced 7-11-86

Plugging Completed 7-11-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS 970 Fourth Financial Center, Wichita, KS 67202

PHONE # (316) 265-3311 OPERATORS LICENSE NO. 5245

Character of Well Oil  
(Oil, Gas, D&A, SHD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? NA If not, is well log attached? YES

Producing formation Mississippi Depth to top 4470' bottom 4489' T.D. 4489'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Mississippi	Oil-Gas-Water	4470'	4489'	5 1/2"	4488'	None
				8 5/8"	521'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Set 20 sx cmt @ 4400'; Pump 250 sx plug from 500' to surface.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Okmar Oil Company License No. 5245

Address 970 Fourth Financial Center, Wichita, KS 67202

STATE OF Kansas COUNTY OF Sedgewick, ss.

Melvyn D. Abels

(operator) of above-described well, being an employee of operator) or I have knowledge of the facts, statements and data herein contained and the log of the above-described well and that the same are true and correct, so help me God.



RECEIVED  
CORPORATION COMMISSION  
RECEIVED  
STATE CORPORATION COMMISSION

7-22-86 (Signature) Melvyn D. Abels  
JUL 22 1986 (Address) 970 Fourth Financial Center

SUBSCRIBED AND SWORN TO before me this 21 day of July, 1986

Amy R. Blecha  
Notary Public

My Commission expires: July 16, 1990

D R I L L E R S      L O G

#1 Bieber

CASING RECORD:  
514.82' of new 8-5/8"  
surface casing.

COMPANY: Okmar Oil Company  
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/SW SE  
Section 30-21S-24W  
Hodgeman County, Kansas

TOTAL DEPTH:  
4489'

COMMENCED: June 14, 1971  
COMPLETED: June 24, 1971

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>	
Clay, Post Rock, Sand & Shale	0	367	Ran 514.82' of new 8-5/8" surface casing; set and cemented at 520.82' with 250 sacks of regular cement, 2% gel and 3% C. C. Plug down at 4:30 A. M. June 15, 1971.	
Clay, Shells & Shale	367	557		
Shale w/Sand Streaks	557	705		
Red Bed, Shale w/Sand Streaks	705	840	5 1/2" casing set and cemented at 4488' with 75 sacks of pozmix, three quarters of one percent CRF2 and 1/8 lb. of nylon. Plug down at 3:40 A. M. June 24, 1971.	
Red Bed & Shells	840	962		
#1 Anhydrite	962	981		
Red Bed and Shale	981	1062		
Dakota Sand	1062	1275		
Red Bed and Shale	1275	1515		
Shale	1515	1575		
#2 Anhydrite	1575	1610		
Shale, & Lime Streaks	1610	1875		
Shale & Shells	1875	2270		
Shells, Shale & Lime	2270	2428		
Lime & Shale	2428	3073		
Shale, Lime & Broken Lime	3073	3163		
Lime & Shale	3163	4363		
Lime	4363	4447		
Lime & Chert	4447	4489		
ROTARY TOTAL DEPTH: 4489'				

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Charles W. Steincamp*  
Charles W. Steincamp, President

Subscribed and sworn to before me this 25th day of June, 1971.

*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public



D R I L L E R S      L O G

#1 Bieber

CASING RECORD:  
514.82' of new 8-5/8"  
surface casing.

COMPANY: Okmar Oil Company  
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/SW SE  
Section 30-21S-24W  
Hodgeman County, Kansas

TOTAL DEPTH:  
4489'

COMMENCED: June 14, 1971  
COMPLETED: June 24, 1971

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay, Post Rock, Sand & Shale	0	367	Ran 514.82' of new 8-5/8" surface casing; set and cemented at 520.82' with 250 sacks of regular cement, 2% gel and 3% C. C. Plug down at 4:30 A. M. June 15, 1971.
Clay, Shells & Shale	367	557	
Shale w/Sand Streaks	557	705	5 1/2" casing set and cemented at 4488' with 75 sacks of pozmix, three quarters of one percent CRF2 and 1/8 lb. of nylon. Plug down at 3:40 A. M. June 24, 1971.
Red Bed, Shale w/Sand Streaks	705	840	
Red Bed & Shells	840	962	
#1 Anhydrite	962	981	
Red Bed and Shale	981	1062	
Dakota Sand	1062	1275	
Red Bed and Shale	1275	1515	
Shale	1515	1575	
#2 Anhydrite	1575	1610	
Shale, & Lime Streaks	1610	1875	
Shale & Shells	1875	2270	
Shells, Shale & Lime	2270	2428	
Lime & Shale	2428	3073	
Shale, Lime & Broken Lime	3073	3163	
Lime & Shale	3163	4363	
Lime	4363	4447	
Lime & Chert	4447	4489	

ROTARY TOTAL DEPTH: 4489'

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

*Charles W. Steincamp*  
Charles W. Steincamp, President

Subscribed and sworn to before me this 25th day of June, 1971.

My Commission Expires:  
December 14, 1973  
ELAINE H. TAYLOR  
NOTARY PUBLIC  
BARTON COUNTY, KANSAS

*Elaine H. Taylor*  
Elaine H. Taylor, Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
CONS. DIV. WICHITA, KS

JUL 22 1971