

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-083-21,293-0000

LEASE NAME LaForce

WELL NUMBER 2-30

1980 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 30 TWP. 21S RGE. 24W (E) or (W)

COUNTY Hodgeman

Date Well Completed 1/5/88

Plugging Commenced 1/4/88

Plugging Completed 1/5/88

LEASE OPERATOR Roadrunner Energy, Inc.

ADDRESS 8908 S. Yale, Suite 360, Tulsa, Oklahoma 74137

PHONE# (918) 495-3933 OPERATORS LICENSE NO. 4555

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filled? yes-together If not, is well log attached? well log with ACO-1

Producing Formation Mississippi - Wet Depth to Top 4532 Bottom T.D. 4585

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippi Lime	water	4524	32	8 5/8	344	0
Mississippi Dolo.	water	4532	36			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
9.0 ppg mud 4585' to 1625', 1625' to 1435': 50 sx 60/40 pozmix w/6% gel, 1435' to 840':  
9.0 ppg mud, 840' to 615': 60 sx 60/40 pozmix w/6% gel, 615' to 345': 9.0 ppg mud, 345' to  
190': 40 sx 60/40 pozmix w/6% gel, 190' to 40': 9.0 ppg mud, 40' to 3': 10 sx 60/40 pozmix  
w/6% gel, 15 sx 60/40 pozmix w/6% gel in rat hole. Job finished at 4:00 A.M. on 1/5/88  
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sage Drilling Co., Inc. License No. 5421

Address 202 S. St. Francis, Wichita, Kansas 67202


STATE OF Kansas COUNTY OF Sedgwick, ss.

Charles Casey Coats agent for Operator  
(Employee of Operator) or (Operator) of  
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,  
statements, and matters herein contained and the log of the above-described well as filed that  
the same are true and correct, so help me God.

(Signature) Charles Casey Coats

(Address) 202 S. St. Francis, Wichita, Ks

SUBSCRIBED AND SWORN TO before me this 14 day of January, 19 88



Peggy A. Clutter  
Notary Public

My Commission Expires: May 11, 1989