


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Hodgeman County, Sec. 27 Twp. 21S Rge. 23W E/W
Location as "NE/CNW $\frac{1}{2}$ SW $\frac{1}{2}$ " or footage from lines
C SW SW

Lease Owner Beren Corporation
Lease Name Bamberger Well No. #1
Office Address 970 Fourth Financial Center, Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) dry hole



Locate well correctly on above
Section Plot

Date Well completed December 21, 1979 19
Application for plugging filed December 21, 1979 19
Application for plugging approved December 21, 1979 19
Plugging commenced December 21, 1979 19
Plugging completed December 22, 1979 19
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas
Producing formation Depth to top Bottom Total Depth of Well 4600'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole plugged with 50-50 pozmix, 6% gel, as follows: 50 sacks @ 900', 35 sacks at 400', hulls and 10 sacks @ 40', 5 sacks in mousehole, 5 sacks in rathole; job completed 1:00 a.m., December 22, 1979

RECEIVED
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)

1-3-80

Name of Plugging Contractor Strata Drilling Company

JAN 3 1980

STATE OF KANSAS COUNTY OF BARTON CONSERVATION DIVISION
Wichita, Kansas, ss.
Charles W. Steincamp (employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of December, 1979.

Loneita Barry
Loneita Barry Notary Public.

My commission expires 3-28-80.



D R I L L E R S L O G

Bamberger #1

CASING RECORD:
10 jts. new 20#
8-5/8" surface
casing.

COMPANY: Beren Corporation

DESCRIPTION: C SW SW
Section 27-21S-23W

CONTRACTOR: Strata Drilling Company Hodgeman County, Kansas

COMMENCED: December 13, 1979

ELEVATION: 2316' GL

TOTAL ROTARY
DEPTH: 4600'

COMPLETED: December 22, 1979

D & A

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand rock, shale	0	415	Ran 399' new 20# 8-5/8" surface casing; set and cemented at 404' with 250 sacks 60-40 pozmix, 2% gel, 3% C.C. Cement circulated. Plug down at 12:10 a.m., December 14, 1979.
Shale	415	1538	
Anhydrite	1538	1571	
Shale	1571	1900	Ran 2 drill stem tests.
Lime and Shale	1900	2950	
Lime	2950	3190	Ran 1 electric log.
Lime and shale	3190	3620	
Lime	3620	3810	Hole plugged with 50-50 pozmix, 6% gel, as follows: 50 sacks @ 900', 35 sacks @ 400; hulls and 10 sacks @ 40', 5 sacks in rathole, 5 sacks in mousehole. Job completed at 1:00 a.m., December 22, 1979.
Lime and shale	3810	4070	
Lime	4070	4210	
Lime and shale	4210	4410	
Lime	4410	4600	

RECEIVED
STATE CORPORATION COMMISSION

JAN - 3 1980

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
)ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Charles W. Steincamp
Charles W. Steincamp

Sworn to and subscribed before me this 27th day of December, 1979.

My appointment expires 3-28-80.

Loneita Barry
Loneita Barry, Notary Public

