

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH

Hodgeman County, Sec. 18 Twp. 21S Rge. (E) 23 (W)
Location as "NE/CNW/SW" or footage from lines C/SW/4
Lease Owner Al Tipton
Lease Name Stairrett Well No. 1
Office Address P. O. Box 157, Hays, Kansas 67601
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed February 21 19 73
Application for plugging filed February 21 19 73
Application for plugging approved February 21 19 73
Plugging commenced February 21 19 73
Plugging completed February 21 19 73
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 10
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves, Sublette, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4530 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD


FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	329.60'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Plugged hole as follows: Plugged at 800' with 80 sacks of common cement; plugged at 320' with 30 sacks of common cement; plugged at 40' with 15 sacks of common cement. Plug down at 10:00 A. M. February 21, 1973.

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1973 3-19-73
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON ss.
Charles W. Steincamp (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Charles W. Steincamp
Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas 67530 (Address)

Subscribed and sworn to before me this 22nd day of February, 1973
Elaine H. Taylor Notary Public

D R I L L E R S L O G

#1 Stairett

CASING RECORD:
323.60' of new 8-5/8"
surface casing.

COMPANY: Al Tipton
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/SW/4
Section 18-21S-23W
Hodgeman County, Kansas

TOTAL DEPTH:
4530'

COMMENCED: February 11, 1973
COMPLETED: February 21, 1973

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay	0	40	Ran 323.60' of new 8-5/8" surface casing; set and cemented at 329.60' with 175 sacks of common cement, 2% gel and 3% C. C. Plug down at 4:00 A. M. February 12, 1973.
Post Rock	40	128	
Shale	128	245	
Sand & Shale	245	710	
Shale & Shells	710	942	
Blaine	942	960	
Shale	960	1040	
Sand	1040	1235	
Shale	1235	1565	
Anhydrite	1565	1599	
Shale & Lime	1599	4484	
Lime, Shale & Chert	4484	4492	
Lime & Shale	4492	4517	
Lime, Shale & Chert	4517	4530	

ROTARY TOTAL DEPTH: 4530'

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1973
CONSERVATION DIVISION
Wichita, Kansas

D. & A.

Plugged hole as follows: Plugged at 800' with 80 sacks of common cement; plugged at 320' with 30 sacks of common cement; plugged at 40' with 15 sacks of common cement. Plug down at 10:00 A. M. February 21, 1973.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 22nd day of February, 1973.

ELAINE H. TAYLOR
NOTARY PUBLIC
My Commission Expires:
December 24, 1973
WICHITA COUNTY, KANSAS

Elaine H. Taylor
Elaine H. Taylor, Notary Public