

15-185-21776-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Stafford SEC. 8 TWP. 23 RGE. 14 E/W
 Location as in quarters or footage from lines:
C S/2 SW SE

Locate Well
 correctly on above
 Section Platt.

Lease Owner The Roxana Corporation
 Lease Name Fischer Well No. 1
 Office Address Box 1162 Great Bend, KS 67530
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed 4-2-83
 Application for plugging filed 4-2-83
 Plugging commenced 4-2-83
 Plugging completed 4-2-83
 Reason for abandonment of well or producing formation _____

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Richard Lacey
 Producing formation _____ Depth to top _____ bottom _____ T.D. 4050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom Plug: @ 3990' w/50 sacks cement thru drill pipe
 Next Plug: @ 870' w/50 " " " " "
 Next Plug: @ 510' w/40 " " " " "
 Top Plug: @ 40' w/bridged plug & 10 sacks cement
 10 sacks cement in Rat Hole
 5 sacks cement in water well

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Lobo Drilling Co.

STATE OF Kansas COUNTY OF Barton, ss.
Ervin Neighbors (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ervin Neighbors
Box 877 Great Bend, KS 67530
 (Address)

SUBSCRIBED AND SWORN TO before me this 6 day of April, 1983

Alvin M. Hoque
 Notary Public.

My Commission expires: 4-29-86

RECEIVED
 STATE CORPORATION COMMISSION

4-7-83

APR 07 1983

CONSERVATION DIVISION
 Wichita, Kansas

15-185-11776-0000

DRILLERS' WELL LOG

DATE COMMENCED: March 25, 1983
DATE COMPLETED: April 2, 1983

The Roxana Corp.
Fischer #1
C S/2 SW SE
Sec. 8, T23S, R14W
Stafford County, Ks.

ELEVATION: 1954 K.B.

0 - 880'	Surface Soil, Sand, Red Bed, Shells, Shale
880 - 901'	Anhydrite
901 - 3417'	Shale & Lime
3417 - 3421'	Shale
3421 - 3441'	Lime & Shale
3441 - 3459'	Lime
3459 - 3550'	Shale
3550 - 3563'	Lime & Shale
3563 - 3779'	Lime
3779 - 3898'	Shale, Lime, Chert, Sand
3898 - 3954'	Chert
3954 - 4012'	Sand
4012 - 4050'	Dolomite
4050'	RTD

FORMATION DATA

Anhydrite	880'
Heebner	3417'
Toronto	3411'
Douglas	3459'
Br. Lime	3550'
Lansing	3563'
Base K.C.	3799'
Conglomerate	3868'
Viola	3898'
Simpson	3954'
Sand	3971'
Arbuckle	4012'
RTD	4050'

Surface Pipe: Set new 8-5/8" 23#,
pipe @459' w/300 sacks 60/40
pozmix, 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 6 day of April 1983.

My Comm. Expires:

4-29-86

d. Dorothy M. Hague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

APR 07 1983

CONSERVATION DIVISION
Wichita, Kansas