

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-20,801-0005

LEASE NAME Snyder

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 2

4290 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 8 TWP. 23S RGE. 14W (Extor (W))

COUNTY Stafford

LEASE OPERATOR F & M OIL CO., INC.

ADDRESS 422 Union Center, Wichita, Ks. 67202

PHONE#(316) 262-2636 OPERATORS LICENSE NO. 5313

Date Well Completed 4-22-78

Character of Well Oil

Plugging Commenced 2/4/86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2/7/86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #1, Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lansing Depth to Top 3564' Bottom 3795' T.D. 4081'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
<u>Lansing</u>	<u>Oil & Water</u>	<u>3564'</u>	<u>3795'</u>	<u>8-5/8"</u>	<u>458'</u>	<u>None</u>
				<u>5 1/2"</u>	<u>4080'</u>	<u>3018'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged bottom with sand to 3630' & 5 sacks cement. Shot pipe at 3018'.

Pulled 76 joints of pipe. Plugged well with 2 hulls, 15 gel, 50 cement, 10 gel, 1 hull, plug, & 140 sacks 60/40 poz 6% gel.

Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 14th day of February, 1986

Irene Hoover
Notary Public

My Commission Expires:



STATE CORPORATION COMMISSION

FEB 18 1986

2-18-86

Form CP-4
Revised 08-84