

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-20,721-6000

LEASE NAME Snyder

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1

3630 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 8 TWP. 23S RGE. 14W (or W)

LEASE OPERATOR F & M OIL CO., INC.

COUNTY Stafford

ADDRESS 422 Union Center, Wichita, Ks. 67202

PHONE#(316) 262-2636 OPERATORS LICENSE NO. 5313

Date Well Completed 7-3-77

Character of Well Oil

Plugging Commenced 1/28/86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2/7/86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dist. #1, Dodge City, Kansas

Is ACO-1 filed? Yes If not, is well log attached? -----

Producing Formation Kansas City Depth to Top 3562' Bottom 3879' T.D. 4081'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Kansas City	Oil & Water	3562'	3879'			
				8-5/8"	292'	None
				4 1/2"	3870'	2774'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

Plugged bottom with sand to 3630' & 4 sacks cement. Shot pipe at 3026', & 2774'.  
Pulled 69 joints of pipe. Plugged well with 2 hulls, 15 gel, 50 cement, 10 gel,  
1 hull, plug, & 140 sacks 60/40 poz 6% gel. Plugging complete.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 10th day of February, 19 86

Irene Hoover

My Commission Expires:



Notary Public RECEIVED 2-13-86  
STATE CORPORATION COMMISSION

FEB 13 1986

Form CP-4  
Revised 08-84