


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD 15-185-301080000

STAFFORD County. Sec. 9 Twp. 23S Rge. 14 (X) (W)

Location as "NE/CNW/SW" or footage from lines: SE NW NE
Lease Owner: PETROLEUM, INC.
Lease Name: BATCHMAN Well No. 1
Office Address: ROUTE #2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole): DRY HOLE
Date well completed: AUGUST 16 19 65
Application for plugging filed: AUGUST 16 19 65
Application for plugging approved: AUGUST 16 19 65
Plugging commenced: AUGUST 16 19 65
Plugging completed: AUGUST 16 19 65
Reason for abandonment of well or producing formation: NO PRODUCIBLE ZONE



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production: NONE 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well: ARCHIE ELYING
Producing formation: _____ Depth to top: _____ Bottom: _____ Total Depth of Well: 3547 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	213'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MUDDED UP WITH HEAVY MUD TO 200', FOLLOWED BY WOODEN PLUG, PLACED 1/2 SACK HULLS AND 25 SACKS CEMENT THROUGH DRILL PIPE ON TOP OF PLUG. MUDDED UP WITH HEAVY MUD TO 40', FOLLOWED BY WOODEN PLUG, PLACED 1/2 SACK HULLS & 10 SACKS CEMENT ON TOP OF PLUG TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1965

8-31-65

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: GARVEY DRILLING CO.
Address: R.R. #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.

(Signature) *Monte Chadd*
R.R. #2, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of AUGUST, 19 65

My commission expires MAY 28, 1969

Richard H. Dangles
Notary Public.

WELL LOG

15-185-30108-0000

COMPANY Petroleum, Inc.

SEC. 9 T. 23S R. 14W

FARM Batchman

NO. 1

LOC. SE NW NE


TOTAL DEPTH 3547'

COUNTY Stafford

COMM. 8-9-65

COMP. 8-15-65

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 213' w/250 sx

ELEVATION 1960' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 40' Surface Soil and Clay
- 110' Sand
- 214' Shale
- 885' Shale, Shells and Red Bed
- 1400' Shale and Shells
- 1560' Shale with Lime Streaks
- 2030' Shale and Lime
- 2210' Lime
- 2330' Lime and Shale
- 2360' Shale with Lime Streaks
- 2760' Shale and Lime
- 3368' Shale with Lime Streaks
- 3547' Lime and Shale
- 3547' RTD

RECEIVED
STATE CORPORATION COMMISSION

AUG 31 1965

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } SS

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Batchman #1 well.

Sam N. Stephens

Subscribed and sworn to before me this 26th day of August 1965

My Commission Expires: May 28, 1969

Richard H. Dumbler
NOTARY PUBLIC