

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-185-21147-0000

LEASE NAME Harper

WELL NUMBER 1

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 9 TWP. 23 RGE. 14 (X) or (W)

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR L. D. Davis Drilling Company

ADDRESS Rt. #1, Box 183-B, Great Bend, Kansas 67530 COUNTY Stafford

PHONE# (316) 793-5831 OPERATORS LICENSE NO. 6039 Date Well Completed 2-25-86

Character of Well Oil Plugging Commenced 2-26-86

(Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging Completed 2-26-86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District 1, Dodge City

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation 3953-70 Depth to Top 3953 Bottom 3970 T.D. 4030

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	280	8 5/8	280	none
	Long string	9	4029	4 1/2	4029	2032

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Bottom sanded to 2900 and capped with 4ks cement. Top 2 hulls, 15 gel, 50 sks c0/40 poz mix. 10 gel, 1 hull, plug 150 sks. 60/40 poz mix max - 200 psi., SIP - 100 PSI

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 768, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

Wes Siroky (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Wes Siroky

(Address) Box 768, Great Bend, Kansas

SUBSCRIBED AND SWORN TO before me this 26 day of February, 19 86

Lovella L. Mullen  
Notary Public

My Commission Expires: 1-13-90



RECEIVED  
STATE CORPORATION COMMISSION

2-27-86 FEB 27 1986

Form CP-4  
Revised 08-84

CONSERVATION DIVISION  
Wichita, Kansas