

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

15-185-12111-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Stafford

County. Sec. 9 Twp. 23S Rge. 14 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SE NE

Lease Owner Stearns Petroleum, Inc.

Lease Name Batchman Well No. 1

Office Address Box 313, Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed January 4, 1955 19

Application for plugging filed January 4, 1955 19

Application for plugging approved 19

Plugging commenced January 4, 1955 19

Plugging completed January 4, 1955 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?

NORTH

Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well M. Rives

Producing formation Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	429	---

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 300'
Plug 1/2 sacks hulls at 300'
20 sacks cement
Mud to 35'
Plug and 1/2 sacks hulls at 35'
10 sacks cement to surface.

CONSERVATION DIVISION
Wichita, Kansas

1-6-55

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stearns Petroleum, Inc.
Address Box 313, Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
D. G. Comstock (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D. G. Comstock

Box 313, Russell, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 4th day of January, 1955

My commission expires April 5-1958 Betty Low Miller Notary Public.

PLUGGING
FILE SEC 9 T 23 R 14 W
BOOK PAGE 29 LINE 3

15-195-12111-0000

BATCHMAN #1 WELL

Contractor: Stearns Petroleum, Inc.
Operator: Phillips Petroleum Company
Commencement Date: December 20, 1954
Completion Date: January 4, 1955

LOCATION: SW SE NE
Section 9-23S-14W,
Stafford County, Kansas

Casing Record:

8 5/8" - 14 joints - 429 feet - Cemented with 225 sacks Pozmix

- WELL LOG -

Sand	0	155
Shale and Shells	155	345
Sand	345	405
Shale and Shells	405	423
Red Bed	423	882
Anhydrite	882	902
Shale and Shells	902	1340
Shale, Shells and Salt	1340	1505
Shale and Shells	1505	1705
Lime and Shale	1705	1741
Shale and Lime	1741	1895
Lime	1895	2080
Lime and Shale	2080	3375
Lime	3375	3470
Shale and Lime	3470	3560
Lime	3560	3605
Heebner Shale	3420	
Brown Lime	3547	
Lansing-Kansas City	3561	
Lime	3605	3880
Shale and Lime	---	---
Lime and Chert	3880	3973
Lime and Shale	3973	3992
Shale	3992	4020
Arbuckle Dolomite	4020	4050
Total Depth:	4050	

STATE OF KANSAS)
) SS:
COUNTY OF RUSSELL)

I hereby certify that the above information is true and correct to the best of my knowledge.

Betty Law Miller

SUBSCRIBED AND SWORN to before me, a Notary Public, this 10th day of January, 1955.

My Commission Expires:

April 5, 1958

Betty Law Miller
Notary Public

PLUGGING
FILE SEC 9 T 23 R 14W
PAGE 89 LINE 3