

15-185-60002-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail: Deliver Report to:  
Conservation Division  
State Corporation Commission  
1001 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 13 Twp. 23 Rge. 14 (E) W (W)

Location as "NE/CNW4SW4" or footage from lines SE SE SE

Lease Owner Texaco, Inc.

Lease Name Malin Well No. 1

Office Address Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19\_\_

Application for plugging filed \_\_\_\_\_ 19\_\_

Application for plugging approved \_\_\_\_\_ 19\_\_


Plugging commenced 4-16-65 \_\_\_\_\_ 19\_\_

Plugging completed 5-20-65 \_\_\_\_\_ 19\_\_

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3782 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	820'	None
				7"	3299'	2783'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to plug-back @ 3682', sanded to 3625' and dumped 5 sacks of cement @ 3625' with dump bailer. Pulled 7" casing, checked hole to 578', mudded hole to 300', set rock bridge to 290' and dumped 30 sacks of cement @ 290'. Mudded hole to 40', set rock bridge to 30' and ran 15 sacks of cement to base of cellar.

6-1-65

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 1 1965  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or ~~owner~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of May, 1965

Milton J. Volin

Notary Public.

My commission expires May 20, 1968

15-185-60002-0000

The Texas Company  
Tulsa, Oklahoma

Tulsa, Oklahoma  
July 21, 1955

CONTRACTOR: Stickle Drilling Company  
Drilling Commenced: July 5, 1955  
Drilling Completed: July 17, 1955

T. A. Malen #1 SE SE SE  
Section 13-23S-14W,  
Stafford County, Kansas.

DRILLERS LOG

Sand	0-50
Shale & Shells	50-265
Sand	265-325
Shale & Shells	325-450
Red Bed	450-811
Anhydrite	811-850
Shale & Shells	850-1665
Lime & Shale	1665-1910
Sand Lime & Shale	1910-2100
Lime & Shale	2100-2350
Lime	2350-2540
Lime & Shale	2540-2695
Shale	2695-2850
Lime & Shale	2850-3151
Lime	3151-3275
Lime & Shale	3275-3455
Shale - Douglas	3455-3494
Lime - K.C.	3494-3520
Lime	3520-3554
Lime - K.C.	3554-3585
Lime	3585-3781 Corrected T.D.

I, Frank E. Stickle, hereby certify the above to be a true and complete Drillers Log of The Texas Company's T. A. Malen #1 SE SE SE Section 13-23S-14W, Stafford County, Kansas.

Edward Gabel  
Notary Public

Frank E. Stickle  
Frank E. Stickle

June 26, 1957  
My Commission Expires

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
503 East Murdock, Wichita, Kansas


15-185-60002-0000

Company: THE TEXAS COMPANY  
Farm: T. A. Malin No. 1

SEC. 13 T. 23 R. 14W  
SE SE SE

Total Depth. 3781 CorrPBTD 3682  
Comm. 7-5-55 Comp. 7-27-55  
Shot or Treated.  
Contractor. Stickle Drilling Co.  
Issued. 10-8-55

County Stafford  
KANSAS



Elevation. 1917 DF

Production. Pump 60 BO, 25 BWPD

CASING:

10 3/4 @ 820' w/ 625 sx cmt.  
7 in. @ 3780' w/ 100 sx cmt.

Figures indicate Bottom of Formations

sand	50
shale & shells	265
sand	325
shale & shells	450
red bed	811
anhydrite	850
shale & shells	1665
lime & shale	1910
sand, lime & shale	2100
lime & shale	2350
lime	2540
lime & shale	2695
shale	2850
lime & shale	3151
lime	3275
lime & shale	3455
Douglas shale	3494
K. C. lime	3520
lime	3554
K. C. lime	3585
lime	3781
Total Depth	Plugged back 3682'

Corrected T.D.

TOPS:

Topeka	2965
Heebner	3353
Toronto	3375
Brown lime	3495
Lansing	3513
Base KC	3757

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 1 1955  
CONSERVATION DIVISION  
Wichita, Kansas