

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15- 185-22,538-0000

LEASE NAME Gleason Ranch

WELL NUMBER 1-13

2970 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 13 TWP. 23 RGE. 14 (X) or (W)

COUNTY Stafford

Date Well Completed 8-3-88

Plugging Commenced 8-3-88

Plugging Completed 8-3-88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR ZPC Petroleum, Inc.

ADDRESS 9319 E. Harry, Suite 122, Wichita, KS 67207

PHONE# (316) 683-8838 OPERATORS LICENSE NO. 4959

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on August 1, 1988 (date)

by Duane Rankin (KCC District Agent's Name)

Is ACO-1 filed? Will be by operator If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3980'

Show depth and thickness of _____ water, oil and gas formations.

OIL, GAS OR WATER CASING RECORD 8-10-88

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

1st plug set @ 830' w/50 sacks cement thru drill pipe

2nd plug set @ 410' w/40 sacks cement thru drill pipe

3rd plug set @ 40' w/10 sacks cement

15 sacks cement in rat hole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Company, Inc. License No. 5929

Address 620 Hubbard, Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.


Leonard Williamson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) 620 Hubbard, Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 9th day of August, 1988

Dorothy M. Hague Notary Public



DRILLERS' WELL LOG

15-185-27538-0600

DATE COMMENCED: July 29, 1988

ZPC Petroleum, Inc.
GLEASON RANCH #1-13
SE SW NW
Sec. 13, T23S, R14W
Stafford County, KS

DATE COMPLETED: August 3, 1988

0	-	72'	Sand
72	-	275'	Shale, Red Bed
275	-	810'	Sand, Red Bed
810	-	838'	Anhydrite
838	-	3029'	Shale, Lime
3029	-	3123'	Lime, Shale
3123	-	3370'	Lime
3370	-	3374'	Shale
3374	-	3408'	Lime
3408	-	3506'	Shale
3506	-	3524'	Lime, Shale
3524	-	3770'	Lime
3770	-	3892'	Shale, Chert, Conglomerate
3892	-	3929'	Chert, Shale
3929	-	3980'	Shale, Sand
		3980'	RTD

Surface Pipe:
Set new 24#, 8 5/8"
at 387' with 200 sacks
60/40 Pozmix, 2% gel,
3% C.C.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss

LEONARD WILLIAMSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Leonard Williamson
Leonard Williamson

SUBSCRIBED AND SWORN to before me this 9th day of August, 1988.



Dorothy M Hague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

AUG 10 1988

CONSERVATION DIVISION
Wichita, Kansas