

**Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitts Building  
Wichita, Kansas**

### WELL PLUGGING RECORD

Stafford

County. Sec. 14 Twp. 23 Rge. XXXX (E) 14 (W)

Location as "NE/CNW/SW" or footage from lines.

Lease Owner Sunray Oil Corporation

Lease Name Proffitt

Office Address Box 195, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 4 19 54

Application for plugging filed	July 7	1954
--------------------------------	--------	------

Application for plugging approved \_\_\_\_\_ July 6 1954

Plugging commenced	July 4	1954
--------------------	--------	------

Plugging commenced	July 4	1954
Plugging completed	July 4	1954

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production. \_\_\_\_\_ 19\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4040 Feet

Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

### CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner		3386		8 5/8	330	none
Toronto		3404				
Brown Lime		3521				
Lansing-Kansas City	water	3534	3787			
Marmaton		3798				
Conglomerate Shale		3866				
Viola		3879				
Simpson		3945				
Arbuckle	water	3996	4040			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded hole from 40' to 300'. Set Halliburton plug, ran 4 sax hulls and 35 sax cement.  
Mudded hole to 40'; set Halliburton plug and ran 15 sax cement.

Well log attached.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Stickle Drilling Company

Address Philtower Building, Tulsa, Oklahoma


STATE OF Kansas, COUNTY OF Barton, ss.  
Robert K. Crouch (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 195, Great Bend, Kansas  
(Address)

SUBSCRIBED AND SWORN to before me this 13 day of July, 1954

**My commission expires**



RECEIVED Notary Public.  
STATE CORPORATION

CONSERVATION DIVISION  
MAY 19 1962

15-185-12113-0000

Sunray Oil Corporation  
Tulsa, Oklahoma

Tulsa, Oklahoma  
July 8, 1954

CONTRACTOR; Stickle Drilling Company  
Drilling Commenced: June 21, 1954  
Drilling Completed: July 4, 1954

C.H. Proffitt #1 900' E.  
of W. Line & 300' N. of S.  
Line Sec. 14-23S-14W,  
Stafford County, Kansas.

DRILLERS LOG

Sand & Clay	5-95
Sand & Shale	95-330
Sand & Red Bed	330-420
Red Bed & Sand	420-1015
Shale & Shells	1015-1600
Salt	1600-1695
Shale & Lime	1695-1740
Lime & Shale	1740-1895
Shale & Lime	1895-2370
Lime & Shale	2370-2480
Shale	2480-2740
Shale & Lime	2740-3370
Lime & Shale	3370-3480
Lime	3480-3550
Lime & Shale	3550-3615
Lime	3615-3755
Lime & Shale	3755-3810
Lime	3810-3847
Lime & Shale	3847-3907
Lime & Chert	3907-3948
Sand & Lime	3948-4000
Lime	4000-4040 TD

I, Fred E. Stickle, hereby certify the above to be a true and complete Drillers Log, of Sunray Oil Corporation's C. H. Proffitt #1 SE-NW-SE-Section 14-23S -14W, Stafford County, Kansas.

Fred E. Stickle  
Fred E. Stickle

Lillian T. Bonham  
Notary Public

February 13, 1956  
My Commission Expires

